

West Bengal Industrial Infrastructure Development Corporation

(Established under W.B. Act XXV of 1974)

Plot No.-10, Block-DJ, Sector-II, Salt Lake City, Kolkata-700 091

Memo No. Infra/Eng/16E-A.M./2021/1007

Dated: 10.04.2023

To**Dhiman Kumar Kanji,
Vill-Ramnagar, PO- Kalatalahat, PS-Ramnagar,
South 24 Pgs, Pin-743504,
West Bengal****Sub: Repairing and Cleaning of 2500 mtr underground RCC hume pipe drainage system at Falta Industrial Park ,Sector-IV under South 24 parganas Division ,Falta WBIIDC, Pin-743504.****Tender Id: Tender Id: 2023_IIDC_491638_1****NOTICE INVITING e-TENDER No. IIDC_24C_2022_2023.****Financial Bid Opened on : 31.03.2023.****Estimated Amount put to tender : ₹28,82,121.00****Rate Quoted : @2.26 % (Two point Two Six percent) less.****Tender Amount : Rs. 28,16,985.00 (Rupees Twenty Eight Lakh Sixteen Thousand Nine Hundred Eighty Five) only.****Time of Completion: 45 (Forty Five) Days.****Dear Sir,**

Your offer **@2.26 % (Two point Two Six percent) less** the rates as shown in the priced schedule of works, for the above mentioned job has been accepted by me for and on behalf of the **West Bengal Industrial Infra-Structure Development Corporation**. The tender has been numbered as **01(C) of 2023- 2024**.

You are, therefore, requested to submit **copies of agreement in duplicate**, in WBIIDC Form No. 1 (available from the office at above address on payment through online **Rs.1180/= per set** of tender documents) within 7 (Seven) days from receipt of this letter failing which your tender will be liable to cancellation. You are also requested to take up the work in consultation with the **OSD & Ex Officio EE (C), South 24 Pgs Division, WBIIDC**, and complete the same within the stipulated period. **The date of commencement of work will be reckoned from 17.04.2023**. You are also requested to submit a detail work programme to the said **OSD & Ex Officio EE (C), South 24 Pgs Division, WBIIDC**. It may be noted that failure from your end to take up and execute proportionate work in proportionate time may invite due action as per provision of bid/tender document.

Apropos Finance Department, Audit Branch, GoWB's Memorandum No.4905-F(Y) dt.17.09.2014, it has now become mandatory to make payment through Electronic Mode (e-Payment) directly to Contractor's account. **The provision of GST will be applicable in this work.**

Security deposit **@ 1 %** will be recovered from the progressive bills to cover security amount equivalent to 3 % of total value of work so executed. 1% (One percent) labour welfare cess will be deducted from each bill / bills.


Statutory deduction will be made for all other taxes from the progressive bills as per Govt. rules and regulation.

You are requested to obtain necessary License, under Contract Labour Rules, from the Labour Commissioner, Govt. of West Bengal and produce the same to the said **OSD & Ex Officio EE (C), South 24 Pgs Division, WBIIDC**.

Thanking you,

Enclo: Schedule of Works.

Yours faithfully,


**Superintending Engineer
WBIIDC**

Percentage BoQ

Tender Inviting Authority: Superintending Engineer, WBIIDC

Name of Work: "Repairing and Cleaning of 2500 mtr underground RCC hume pipe drainage system at Falta Industrial Park ,Sector-IV under South 24 parganas Division ,Falta WBIIDC"

Contract No:

PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMB ER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words
1	2	4	5	6	54	55
1.00	Cleaning rubbish, sludge, weeds scum, liquidearth, mud etc. from conduits of any dia. above 900 mm and from any depth, etc. by mator labour after removing concrete slab / manhole cover etc. without damaging the same and refixing the same properly after cleaning as necessary and removing the sludge etc. by using iron pans, buckets including all labour, tools & plants including expulsion of impure / inflammable / asphyxiating gases from the drains etc. and removing the spoils in dry condition and disposing the same by truck beyond the area of Municipal Corporation / Municipality / Notified Area Authority / Industrial Township Authority etc. unloading, transportation and making arrangements in all respects, complete as per direction of the Engineer-in-Charge (Land for disposal to be arranged by the contractor. (Payment will be made on the basis of actual stack measurement of spoils in dry condition at roadside.	531.6	Cum	344.43	183098.99	INR One Lakh Eighty Three Thousand & Ninety Eight and Paise Ninety Nine Only
2.00	Earth work in excavation of foundation trenches or drains or septic tank , soak wells etc. in all sorts of soil (including mixed soil but excluding laterite and sand stone), including removing spreading or stacking the spoils within a lead of 75 metre as directed and including trimmng the sides of trenches, levelling, dressing and ramming the bottom, bailing out water etc. as required complete. a) Depth of excavation not exceeding 1500mm	78.19	Cum	142.14	11113.93	INR Eleven Thousand One Hundred & Thirteen and Paise Ninety Three Only
2.10	b) Depth of excavation exceeding 1500 mm but not exceeding 2000 mm	10.57	Cum	229.27	2423.38	INR Two Thousand Four Hundred & Twenty Three and Paise Thirty Eight Only
3.00	Single brick flat soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with powered local sand.	50.2	Sqm	426.66	21418.33	INR Twenty One Thousand Four Hundred & Eighteen and Paise Thirty Three Only
4.00	cement concrete (mix - 1:3:6) with graded stone ballast (40mm mm nominal size) excluding shuttering and reinforcement if any as per relevant I.S. codes. A) With Pakur variety.	7.53	Cum	6185.44	46576.36	INR Forty Six Thousand Five Hundred & Seventy Six and Paise Thirty Six Only
5.00	Brick work with first class bricks in cement mortar (6: 1) including cost of scaffolding and other incidental work etc. complete. i) In foundation and plinth	131.71	Cum	6323.69	832893.21	INR Eight Lakh Thirty Two Thousand Eight Hundred & Ninety Three and Paise Twenty One Only

6.00	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams, columns, lintels, curved or straight including fitting and fixing and striking out after completion of works. A. 25mm to 30mm shuttering without staging in foundation etc.	24.525	Sqm	249.08	6108.69	INR Six Thousand One Hundred & Eight and Paise Sixty Nine Only
6.10	B. 25 mm to 30mm thick wooden shuttering as per decision & direction of Engineer Incharge	209.74	Sqm	399.25	83738.7	INR Eighty Three Thousand Seven Hundred & Thirty Eight and Paise Seventy Only
7.00	Ordinary cement concrete (mix - 3 : 1.5 : 1) with graded stone chips (20 mm mm nominal size) excluding shuttering and reinforcement if any as per relevant I.S. codes. A) With Pakur variety.	30.4513	Cum	7155.98	217908.89	INR Two Lakh Seventeen Thousand Nine Hundred & Eight and Paise Eighty Nine Only
8.00	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups binders etc. including supply of rods, initial straightening and removal of loose rust (if necessary) cutting to requisite length hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection complete as per drawing direction including cost of wire. tor steel/mild steel(Other than SAIL/TATA/RINL) a) upto Ground floor roof level upto 4m	2.39	MT	65607.36	156801.59	INR One Lakh Fifty Six Thousand Eight Hundred & One and Paise Fifty Nine Only
9.00	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary . 1(i) (b) with 6:1 cement mortar i) 15 mm thick plaster	264.32	Sqm	172.811	45677.4	INR Forty Five Thousand Six Hundred & Seventy Seven and Paise Forty Only
10.00	Neat cement punning about 1.5 mm thick in wall, dado, window sills, floor, drain etc.	264.32	Sqm	40.52	10710.25	INR Ten Thousand Seven Hundred & Ten and Paise Twenty Five Only
11.00	Supplying, fitting and fixing in position reinforced cement polymer concrete manhole /gully pit coverwith matching frame. As per I.S-12592(M.D)i) 15 MT load bearing capacity gully pit cover withframe and hinge arrangement for opening of sizeCover : 565 mm. X 410 mm. X 90 mm.Frame : 715 mm. X 565 mm. X185 mm. weight:140	306	Each	4129.58	1263651.48	INR Twelve Lakh Sixty Three Thousand Six Hundred & Fifty One and Paise Forty Eight Only
Total in Figures					2882121	INR Twenty Eight Lakh Eighty Two Thousand One Hundred & Twenty One Only
Quoted Rate in Figure			Select		0.00	INR Zero Only
Quoted Rate in	INR Zero Only					


 Superintending Engineer
 WBIIDC